

## **ADAM MOREHOUSE**

## PROJECT:510 E SANTA PAULA ST., SANTA PAULA CA

DATE	DESCRIPTION	AMOUNT
7/15/24	OVER-EXCAVATION OPERATION	\$6,950.00
	Excavate for proposed detached garage, backfill and compact to pad grad	le
	•Over-excavate 4 below existing grade and 5 feet beyond building	
	perimeter, per Heathcote soil report, civil plan not available at this time.	
	•Backfill and compact in 2 ft lifts, including compaction testing	
	every 2 ft.	
	• Remove existing grass, and vegetation. Haul debris off-site.	
	• KX 121 Excavator, pad foot compactor, bobcat loader, labor and operat	tor
	*If rock, or concrete is encountered during over-excavation it will be an extra	
	to remove for backfill. Estimate does not include underground utilities install or	
	potholing.	
	IMPORT	\$150.00 PER LOAD
	Shrinkage is expected during compaction and there may be a need	
	for import to get garage pad to proposed grade. Approval to be made by	
	Heathcote soil tech.	
	*Payments are billed bi-weekly and due upon receipt, please.	